BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/22/2020-21, Date:17.11.2020

SCHEDULE-B

NAME OF WORK: Repair to Toilet and providing sanitary and Water supply pipe lines to Existing borewell in ward No 12

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri SHANTHKUMAR P (INCHARA CONSTRUCTIONS)	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation for pipeline trenches including depositing on bank upto a lead of 50 mtrs and depth up to 2.00 mtrs. Including shoring and strutting, danger lighting and using sight rails and boning rods at every 100 mtrs. Wherever necessary as directed in the following strata. (Manual Means) in ordinary soil etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	1952.25	200.0	Rupees Two Hundred Only
2	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs with 20mm and down size graded granite metal coarse aggregate @ 0.84cum and fine aggregate @ 0.56 cum machine mixed concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Rmt	3425.00	138.0	Rupees One Hundred Thirty Eight Only
3	Refilling the basement and pipeline trenches with selected available earth from trench excavation including watering, Consolidation in layers of 15 cm thick including disposing of the surplus earth with all lead & lifts. (Compacting with vibro roller) etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	1952.25	91.0	Rupees Ninety One Only
4	Supply and delivery at site of brand new best make gate valve as per IS 778/1984 with ISI Mark and as per its latest amendments etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Each	80.00	1000.0	Rupees One Thousand Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division.